

Search for Single Top Quark Production at DØ

Ernest Aguiló

on behalf of the DØ Collaboration

Pheno 2006 Symposium

University of Wisconsin, Madison,
May 16, 2006



UNIVERSITY OF
ALBERTA
EDMONTON, ALBERTA, CANADA



YORK
UNIVERSITÉ
UNIVERSITY
redefine THE POSSIBLE.


Outline

- Introduction & Motivation
- Background & Modeling
- Event selection
- Signal/Background separation
- Results
- Current Status
- Conclusions & Outlooks




Introduction

Motivation:



$$\sigma_{NLO} = 0.88 \pm 0.14 pb$$




$$\sigma_{NLO} = 1.98 \pm 0.30 pb$$

- Direct measurement of $|V_{tb}|$
- Test SM and unitarity of CKM

- Measure top quark properties
- New Physics


Introduction

Event Signature:



$$\sigma_{NLO} = 0.88 \pm 0.14 pb$$

- One high p_T isolated lepton
- Missing Transverse Energy



$$\sigma_{NLO} = 1.98 \pm 0.30 pb$$

- One b quark jet
- A light flavor and/or another b jet



Background & Modeling

- **Background:**

- Main source: W +jets & $t\bar{t}$
- Also: multijet (missidentified lepton) & diboson (WW/WZ)

- **Modeling:**

- Signal: effective NLO COMPHEP
 - $t\bar{t}$: ALPGEN
 - diboson: ALPGEN
 - W +jets: ALPGEN + data (normalization)
 - Multijet: from data
- } + PYTHIA



Event selection

- **Cuts:**

- 1 isolated lepton: $p_T > 15 \text{ GeV}$

$$|\eta_e| < 1.1 \quad |\eta_\mu| < 2.0$$

- MET > 15 GeV

- Jets: $2 \leq N \leq 4$ $E_T > 15 \text{ GeV}$

$$|\eta| < 3.4 \quad E_T(\text{jet1}) > 25 \text{ GeV}$$



- 1 tightly b-tagged jet (see next slide)

- Other clean-up cuts




Event selection

- **B-tagging:**
 - Use Jet Lifetime Probability (JLIP)



Event selection

- Performance (370 pb^{-1}):
 - Expected yields:




- Selected data:

- Before b-tagging $\sim 10^4$ evt.
- After b-tagging 443 evt.



Event selection

- Performance (370 pb^{-1}):
 - Good agreement:



- Selected data:

- Before b-tagging $\sim 10^4$ evt.
- After b-tagging 443 evt.




Signal/Background Separation

- Still huge background \rightarrow need multivariate analysis.
- In this analysis: Likelihood discriminants...


$$L = \frac{P_{\text{signal}}(\vec{x})}{P_{\text{signal}}(\vec{x}) + P_{\text{background}}(\vec{x})} ; P(\vec{x}) = \prod_{\text{vars}} P(x_i)$$

- Variables \rightarrow good signal/background discrimination:

DØ Run II Preliminary, 370 pb⁻¹



DØ Run II Preliminary, 370 pb⁻¹





Signal/Background Separation

- Still huge background \rightarrow need multivariate analysis.
- In this analysis: Likelihood discriminants...


$$L = \frac{P_{\text{signal}}(\vec{x})}{P_{\text{signal}}(\vec{x}) + P_{\text{background}}(\vec{x})} ; P(\vec{x}) = \prod_{\text{vars}} P(x_i)$$

- Variables \rightarrow good signal/background discrimination:




Signal/Background Separation


- 16 likelihoods (7-10 variables in each):



DØ Run II Preliminary, 370 pb⁻¹




DØ Run II Preliminary, 370 pb⁻¹



Results

- Single top quark production not observed
- 95% CL limits calculated with a Bayesian approach
- Use 2D histograms as input for binned likelihood
- Use shape information from Likelihood output
- Systematics and correlations included



$$\sigma_{NLO} = 1.98 \pm 0.30 \text{ pb}$$

$$\sigma_{NLO} = 0.88 \pm 0.14 \text{ pb}$$




Current Status

- Current upper limits:

		s-channel	t-channel
DØ Lhood 370/pb	Observed	5.0	4.4
	Expected	3.3	4.3
CDF NN 695/pb	Observed	3.2	3.1
	Expected	3.7	4.2

- Study sensitivity to models beyond the SM:



Conclusions & Outlooks


- Single top quark production not yet observed but very tight constraints to the Standard Model are being set.
- Already sensitive to new Physics.
- The DØ RunII search is improving:
 - Better calorimeter calibration.
 - Better jet energy scale.
 - Improved b-tagging.
 - NNs, decision trees, matrix element analyses.
 - Results with 1 fb^{-1} soon.
 - **Getting very close to observation!**



Backup slides



DØ for Run II




Data Taking




Run II Integrated Luminosity

19 April 2002 - 20 January 2006



Ernest Aguiló

Tevatron Luminosity Prospects



W+jets normalization

- ▶ Find fractions of real and fake isolated ℓ in the data before b-tagging. Split samples in loose and tight isolation:

$$N^{loose} = N_{fake}^{loose} + N_{real}^{loose}$$

$$N^{tight} = \varepsilon_{fake} N_{fake}^{loose} + \varepsilon_{real} N_{real}^{loose}$$

Obtain: N_{real}^{loose} and N_{fake}^{loose}

- ▶ Normalize the MC Wjj and Wbb samples to the real ℓ yield found in data, after correcting for the presence of tt and diboson events:

$$\varepsilon_{real} N_{real}^{loose} = SF [Y(Wjj) + Y(Wb\bar{b})] + Y(t\bar{t}) + Y(WW) + Y(WZ) \quad SF=1.05$$

- ▶ The sum $Y(Wjj) + Y(Wbb)$ is done according to the NLO ratio of cross sections (MCFM) before b-tagging \rightarrow 25% uncertainty
- ▶ Then apply b-tagging
 - ▶ Greatly reduce W+jets background (Wbb \sim 1% of Wjj)
 - ▶ Shift distributions, changes flavor composition



Systematic Uncertainties

Monte Carlo Systematic Uncertainties

Theory cross sections	15%
SVT modeling, single (double) tag	10%(20%)
Jet Energy Scale	10%
Trigger Modeling	6%
Jet Fragmentation	6%
Jet ID	5%
ℓ ID	5%



► Some systematic uncertainties also affect shape:

JES, b-tag and trigger modeling

► Total uncertainty:

	1 tag	2 tags
Signal acceptance	15%	25%
Background sum	10%	26%

► Result is statistics limited





Limits from Binned Likelihood

- ▶ No evidence for single top signal
- ▶ Set 95% CL upper cross section limit with Bayesian approach
- ▶ Use 2D histograms as input for binned likelihood
- ▶ Including bin-by-bin systematics and correlations


Used for DT and NN analyses

Cut-based analysis uses likelihood from event count



Sensitivity

With current analysis, we would need several fb^{-1} for an observation of SM single top



Need to work on many fronts to improve:

- ▶ Trigger efficiency
- ▶ Object ID: e , μ , jet, b
- ▶ Jets resolution
- ▶ Add more channels
- ▶ Background estimation
- ▶ Reduction of systematics
- ▶ Bkgnd-signal separation



Bayesian Probability

Bayes' theorem expresses the degree of belief in a hypothesis A, given another B. "Conditional" probability $P(A|B)$:

$$P(A|B) = \frac{P(B|A)P(A)}{P(B)}$$

In HEP: $B \rightarrow N_{\text{observed}}$, $A \rightarrow n_{\text{predicted}} = n_{\text{signal}} + n_{\text{bkgd}}$, $n_s = \text{Acc} * L * \sigma$

$P(B|A)$: "model" density, or likelihood: $L(N_{\text{observed}} | n_{\text{predicted}}) = n^N e^{-n} / N!$

$P(A)$: "prior" probability density $\prod(n_{\text{pred}}) = \prod(\text{Acc} * L, n_b) \prod(\sigma)$
 $\prod(n_s, n_b)$ multivariate gaussian ; $\prod(\sigma)$ assumed flat

$P(B)$: normalization constant Z: $P(N_{\text{observed}})$

$P(A|B)$: "posterior" probability density $P(n_{\text{predicted}} | N_{\text{observed}})$

$$P(n_{\text{predicted}} | N_{\text{observed}}) = 1/Z L(N_{\text{observed}} | n_{\text{predicted}}) \prod(n_{\text{pred}})$$



Preparing the Way for the LHC

Studies at the Tevatron will help the LHC:

- ▶ **Wbb measurement (will also help WH search)** (DØ: [hep-ex/0410062](#))
Current limit at 4.6 pb for $p_T(b) > 20\text{GeV}$
- ▶ **In general, W+jets background determination techniques**
tt will be main background, but large uncertainties come from W+jets
Effect of jet vetoes ($N_{\text{jet}}=2$), check other methods planned in LHC analyses
- ▶ **Study charge asymmetries** (Bowen, Ellis, Strassler: [hep-ph/0412223](#))
Signal shows asymmetry in $(Q_e \times \eta_j, Q_e \times \eta_e)$ plane at TeV
- ▶ **Study kinematics of forward jets in t-channel (WW→H at LHC)**
- ▶ **Even measure asymmetry in production rate** (Yuan: [hep-ph/9412214](#))
(probe CP-violation in the top sector):

$$A_t = \frac{\sigma(p\bar{p} \rightarrow tX) - \sigma(p\bar{p} \rightarrow \bar{t}X)}{\sigma(p\bar{p} \rightarrow tX) + \sigma(p\bar{p} \rightarrow \bar{t}X)}$$

